

The Odisha Gazette



EXTRAORDINARY
PUBLISHED BY AUTHORITY

No. 1884 CUTTACK, TUESDAY, JULY 1, 2025/ASADHA 10, 1947

FOREST, ENVIRONMENT & CLIMATE CHANGE DEPARTMENT

NOTIFICATION

The 30th May 2025

S.R.O. No. 381/2025—Whereas, Forest Block Jhadinga (A) Reserve Forest under Section 21 of the Odisha Forest Act, 1972, has been notified by Government of Odisha, Revenue Department Notification No. S.R.O. No.731/82-R., dated the 12th September 1982 indicating an area of 100.50Ac. in Boipariguda Forest Range of Jeypore Forest Division as per Annexure-I;

And whereas, the Government of Odisha in the Forest & Environment Department have notified a “Standard Operating Procedure (SOP) for geo-referencing of Forest Block boundary through DGPS Survey” in the *Odisha Gazette* vide Notification No. 22572400112016-10F (Cons)-77/2016/14097-F&E, dated the 4th July 2017, for preparation of such geo-referenced forest maps in pursuance of the directives of Hon’ble Supreme Court in their order dated the 6th July 2011 [in IA Nos. 1868, 2091, 2225—2227, 2380, 2568 and 2937 in Writ Petition (C) No. 202 of 1995 - Lafarge matter];

And whereas, the Government of Odisha have appointed all Tehsildars in their respective Tehsil jurisdiction in the respective Districts as Forest Settlement Officer (FSO) vide Notification No. 7767—10F(TR)38/2020-F&E, dated the 21st May 2020;

And whereas, the Forest Revenue Joint Verification Committee has jointly verified and confirmed the boundary pillar positions as per report in Annexure-II;

And whereas, the Forest Settlement Officer has certified ‘No Change’ in the boundary extent of Jhadinga (A) RF post 25th October 1980. The DGPS survey boundary co-ordinates have been verified by ORSAC and certified by the Forest Settlement Officer. The computed area (UTM Zone 44N projection and WGS 84 datum) of the Jhadinga (A) RF is 41.054ha or 101.45Ac. The change in area is due to Method of Survey & Area Computation.

Therefore, it has been decided to supplement the existing notification of the Jhadinga (A) RF with the above-mentioned FSO certified DGPS surveyed Forest Block map as per Annexure-III, and the statement of geo-co-ordinates of the Forest Block boundary pillar positions

as per Annexure-IV, which shall be treated as the precise boundary description of the Jhadinga (A) RF and shall form an intergal part of the original notification in place of any other form of boundary description notified earlier.

There shall be no change to the admitted rights in the original notification.

[No. 12497—FE-DIV-MISC-0011/2016-10F(Cons.)-34/2020-FE & CC]

By order of the Governor

SATYABRATA SAHU

Additional Chief Secretary to Government

(4) The land shall be reserved for the purpose of the Reserve Forest and shall be managed as such.

(5) The right to enjoy the land of the Reserve Forest shall be decided by the Government of the State in accordance with the provisions of the Forest Act, 1927.

(No. 1000-1-115-100)

By order of the Government

MR. SARWAR

Deputy Secretary to Government

REVENUE DEPARTMENT NOTIFICATION

The 12th September 1953

By Order No. 711/82-10.—In exercise of the powers conferred under Section 21 of the Forest Act, 1927, the State Government do hereby declare that the land situated in the village of Jyotiraj, the limits of which are specified below and the approximate area of which is 100.50 acres, shall be a Reserve Forest with effect from 1st October 1953 and shall be known as JYOTIRAJ Reserve Forest.

Name of the Area in acres	Local names & boundaries	Police Station	Taluk Division	District
(1)	(2)	(3)	(4)	(5)
JYOTIRAJ VILLAGE 100.50	North—Jyotiraj No. 50 South—Chaliguda No. 49 East— West—Jyotiraj No. 50	Jyotiraj	Jyotiraj	Jyotiraj

DETAILED BOUNDARY DESCRIPTION

Police No.		Bearing		Distance	
From	To	Degrees	Minutes	Chains	Feet
1	2	31	00	16	92
2	3	110	00	2	30
3	4	110	30	3	60
4	5	159	00	2	92
5	6	114	30	2	60
6	7	157	00	2	92
7	8	202	30	2	60

Pillar No.	To	Bearing		Distance	
		Degrees	Minutes	Chains	Links
1	2	212	00	6	30
2	3	270	30	3	00
3	4	270	00	3	00
4	5	234	00	4	00
5	6	234	00	4	00
6	7	307	00	9	00
7	8	263	00	6	00
8	9	1	00	8	00
9	10	360	00	7	00

2. The State Government do hereby further declare that the rights admitted in respect of BHADINGA reserve forest detailed in the schedule below.

Name of the Forest Block	SCHEDULE	Rights admitted
BHADINGA 'A'	The right to enjoy fruits of horticultural plantation permitted within the boundary of the R.P. may be decided by the Collector of the district in consultation with D. F. O. concerned would be available to the village community or to specified individuals who include their successors in interest.	

[No. 66463—P. S. 317—1-R.]

By order of the Governor

Sd. SARWAR

Deputy Secretary to Government

REVENUE DEPARTMENT

NOTIFICATION

The 12th October 1982

S.R.O. No. 73282-R.—In exercise of the powers conferred under Section 31 of the Forest Act, 1972, the State Government do hereby declare that the land situated in Bhadinga Tehsil of the district of the Kovvur, the limits of which are specified below and the approximate area of which is 53.80 acres shall be reserved forest with effect from the 25th October 1982 and shall be known as Kalliguda Extension Forest Block.

Name of the Forest Block	Area in acres	Local names & boundaries	Police Station	Forest Division	District
KALLIGUDA EXTENSION FOREST BLOCK	53.80 acres	North—Kalliguda No. 31 South—M. A. I. d. II No. 31 West—M. A. I. d. II No. 31 East—Kalliguda R. P.	Bhadingamma	Nowrangpur	Kovvur

The limits of the reserve forest are the lines marked in green on a copy of each of the 1:50,000 scale maps of the villages specified below which has been signed by the Collector of the district and deposited in the Record Room.

Name of the Village	Name of P. S.	Thana No.	No. of Maps
1. M. A. I. d. II	Bhadingamma	No. 31	One

P. O. No. 384-S-1982

FOREST REVENUE JOINT VERIFICATION COMMITTEE REPORT

Forest Division: Jeypore**Forest Range:** Boipariguda**Minutes of Joint Verification:**

List of participation of the Forest-Revenue joint verification committee is given at Table 1.



Joint Verification of the boundary of **Jhadinga (A) RF** Forest Block was carried out during 14-02-2020 to 14-02-2020. Existing pillar position recorded through GPS were plotted and compared against geo-referenced cadastral maps of adjoining villages. The verified forest boundary map is enclosed at Plate-1. Findings of the verification w.r.t. revenue cadastral is given below:


- Name of notified forest block: Jhadinga (A) RF
- Notification no. & date: SRO No. 731/82 -R. Dt. 12-09-1982
- Area as per notification: 100.50 Ac.
- Existing no. of boundary demarcations in conformity with adjoining village boundary: 5 nos. (Annexure -1)
- Boundary demarcations (Proposed Pillars) in conformity with adjoining village boundary: 14 nos. (Annexure -2)
- GPS area of verified boundary: 41.143 ha
- GPS perimeter of verified boundary: 2.635 km

Observations:

Notification with detailed boundary description and Traverse map with Chainage & Bearing is enclosed at Appendix-1 & Appendix-2 The verified boundary shape & area matches with the Traverse map (Diff is 0.47 ha, i.e. 1.16 %). Forest boundary demarcation Pillars in Conformity with Cadastral Map, existing pillars & HRSL. Change area is due to method of Survey and Area computation.

TABLE-1

Forest/ Revenue dept. officials (RO/FR/FG/RI/Amin) & TP present during Joint verification of Forest Boundary		
Name	Designation	Signature
Miss. Dibya Madhury Sethy	RO, Boipariguda	<i>Dibya</i> Forest Range Officer Boipariguda Range
Sri Bikash Patra	Forester, Boipariguda	<i>B. Patra</i>
Ramesh pradhan	CDLTP Coordinator	<i>R. Pradhan</i>
Sabitarami Nayak	I/c R.I (Massigam)	<i>Sabitarami</i> REVENUE INSPECTOR MASSIGAM
<p align="center"><u>Counter Signed by:</u></p> <div style="display: flex; justify-content: space-between; align-items: flex-end; padding-top: 20px;"> <div style="text-align: center;">  2-12-20 Divisional Forest Officer Jeypore Forest Division </div> <div style="text-align: center;">  2/12/2020 TAHASILDAR KUNDRA </div> </div>		



Geo-referencing of Notified Forests in
Jeypore Forest Division
Reference Forest Block Boundary Map
w.r.t Adjacent Revenue Village (Cadastral) Boundary
(based on Forest Revenue Jt. Verification)

Jhadinga (A) R.F., Boipariguda Range



0.1 0 0.1 0.2 0.3 0.4 km



Scale: 1:10,000

Legend

- Existing Pillar (5nos) ✕ Rejected Pillar (0 nos)
- New Pillar (14 nos) □ RF Boundary
- Virtual Pillar (1 nos) - - - Village Boundary

Index Map



Jeypore Forest Division

Notified Area
= 40.672 ha.
GPS area* as per joint verification = 41.143ha.
(* Projected area in UTM Proj. Zone 44N & WGS 84 Datum)

Surveyor
(CDLTP)

Forester


Revenue Pectr Range
Inspector

Date: 10-Feb-2020
Prepared by: SPARC Pvt. Ltd. (CDLTP) Koraput Office
MASSIC Forest Range
Boipariguda Range

FSO Certified DGPS Surveyed Forest Block Map

Annexure-III

8



STATEMENT OF GEO-COORDINATES OF PILLAR POSITIONS

Forest Division: **Jeypore** Forest Range : **Boipariguda** Forest Block Name: **Jhadinga (A) RF****Ground Control Point (GCP) References. (All coordinates in WGS84 datum & UTM Zone 44N projection)**

GCP Type	GCP Location	Latitude(DMS)	Longitude(DMS)	Latitude(DD)	Longitude(DD)
FPCP	Boipariguda Range Office	18°45'4.185396"	82°25'47.792316"	18.75116261	82.42994231
FSCP1	Jhadinga (A) RF, Pillar No- 1	18°51'41.176656"	82°26'58.122492"	18.86143796	82.44947847

Geo-coordinates of Boundary Pillar Position (Total: 19 nos.)

Pillar No	Latitude(DMS)	Longitude(DMS)	Latitude(DD)	Longitude(DD)
1	18°51'41.176656"	82°26'58.122492"	18.86143796	82.44947847
2	18°51'42.534324"	82°26'59.643240"	18.86181509	82.44990090
3	18°51'45.549396"	82°27'3.220452"	18.86265261	82.45089457
4	18°51'48.543588"	82°27'7.254900"	18.86348433	82.45201525
5	18°51'46.578564"	82°27'12.474252"	18.86293849	82.45346507
6	18°51'44.961120"	82°27'17.136972"	18.86248920	82.45476027
7	18°51'44.081712"	82°27'20.226780"	18.86224492	82.45561855
8	18°51'39.066408"	82°27'23.230512"	18.86085178	82.45645292
9	18°51'34.930296"	82°27'25.651188"	18.85970286	82.45712533
10	18°51'34.254216"	82°27'27.209952"	18.85951506	82.45755832
11	18°51'29.359692"	82°27'27.776592"	18.85815547	82.45771572
12	18°51'25.656948"	82°27'27.817596"	18.85712693	82.45772711
13	18°51'26.620704"	82°27'22.204980"	18.85739464	82.45616805
14	18°51'26.940888"	82°27'15.830784"	18.85748358	82.45439744
15	18°51'26.262396"	82°27'12.266640"	18.85729511	82.45340740
16	18°51'28.910772"	82°27'8.871264"	18.85803077	82.45246424
17	18°51'32.037552"	82°27'3.366936"	18.85889932	82.45093526
18	18°51'31.027608"	82°26'58.575660"	18.85861878	82.44960435
19	18°51'35.165808"	82°26'58.473204"	18.85976828	82.44957589

*** END of Statement***